

Faculty Bldg

ESTIMATE FOR LOCAL FURNITURE IN CLASSROOMS & FACULTY BUILDING IN G				
Sr No	Description	Quantity	Unit	Rate
CLASSROOMS				
1	Teaching stage of size 3500X1500X250mm made from 12mm thik marine plywood and 12mm T W planks resting on suitable teak wood frame with step with hand polishing etc complete	26.25	Sqm	
2	same as above but size 1800X1500X250mm	13.5	Sqm	
3	Pelmet above writing board/window made out of 12mm commercial plywood with laminate of approved shade from outside and hand polishing from inside with necessary bidding pattis and hanging arrangement	200	Rmt	
4	Providing & fixing 25mm dia SS heavy duty curtain rail with PVC curtain rings with all necessary SS beackets, screws etc completel	175	Rmt	
	Providing and fixing vinitian blinds of approved make and as per approved sample	175	Sqm	
5	Chalk & duster tray 400mm long made out of 12mm commercial plywood laminated from both sides of approved shade with necessary bidding pattis and hanging arrangement	10	Nos	
6	Wirting white boards of size 1800X1200mm in powder coated aluminium rectangular frame with necessary fixtures	5	Nos	
7	same as above but in size 3500X1500mm	4	Nos	
FACULTY BUILDING				
1	Teaching stage of size 1800X1350X250mm made from 12mm thik marine plywood and 12mm T W planks resting on suitable teak wood frame with step with hand polishing etc complete	5	Sqm	
2	same as above but size 1500X1200X250mm	7.5	Sqm	
3	Pelmet above writing board/window made out of 12mm commercial plywood with laminate of approved shade from outside and hand polishing from inside with necessary bidding pattis and hanging arrangement	185	Rmt	
4	Providing & fixing 25mm dia SS heavy duty curtain rail with PVC curtain rings with all necessary SS beackets, screws etc completel	175	Rmt	
5	Chalk & duster tray 500mm long made out of 12mm commercial plywood laminated from both sides of approved shade with necessary bidding pattis and hanging arrangement	6	Nos	

Faculty Bldg

6	Wirting white boards of size 1800X1200mm in powder coated aluminium rectangular frame with necessary fixtures	2	Nos	
7	same as above but in size 1500X1200mm	4	Nos	
8	Providing and fixing 80mm thk gypsum partition comprising of two gypsum sheets fitted on G. I. Sections and filled with dense fibre glass wool to ensure that sound does not pass through the partition.	90	Sqm	
9	Providing and laying gypsum false ceiling in heavy duty GI section frames and suspended securedly tightened in ceiling above in toilets.	85	Sqm	
10	Providing trap doors in false ceiling with proper opening and hinge arrangement all as approved	8	Nos	
11	Providing and fixing vertical blinds of approved make with all heavy duty tilting and folding assembly	650	Sqm	
12	Same as above but bamboo roller blinds	525	Sqm	
13	Partition 40mm thk made up of T W frame and 6mm commercial plywood from both sides and laminated from all sides up to ceiling. The partitions shall be provided with fixed 8mm thk clear float glass panels as per instructions	175	Sqm	
14	Extra for containing sliding door of same material of partition with guide rail lock, concealed handle etc complete	10	Nos	
15	Providing and fixing raised access flooring comprising of gridded metal pedestals to support liftable floor panel of 2'X2' size and of approved make sufficient to take the designed load. The raised flooring shall be in rooms of hexagonal shape and proper support system may be designed along inclined sides. The height of raised flooring shall be between 300 to 450mm. The flooring shall be provided with three nos of panel lifter	270	Sqm	
		Total		
		MVAT 5%		
		S Tax 6%		
		Gross Total		
		Signature		
		Seal		

UWAHATI
Amount

Faculty Bldg
