

| Quote for painting of common walls and compound wall of Hyderabad Campus |                                                                                                                                                                                                                                                         |      |          |       |                  |
|--------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|-------|------------------|
| DSR 2018<br>vol. I/II<br>item no                                         | Particulars of Items                                                                                                                                                                                                                                    | Unit | Quantity | Rate  | Amount           |
| <b>13</b>                                                                | <b>FINISHING (PAINTING)</b>                                                                                                                                                                                                                             |      |          |       |                  |
| 13.46                                                                    | exterior paint of required shade :                                                                                                                                                                                                                      |      |          |       |                  |
| 13.46.1                                                                  | New/old work (Two coats applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm                                                                                                                           | Sqm  | 248      | 164.7 | 40845.6          |
| 13.81                                                                    | Distempering with 1st quality acrylic distemper, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. |      |          |       |                  |
| 13.81.2                                                                  | Two coats                                                                                                                                                                                                                                               | Sqm  | 923      | 81.9  | 75593.7          |
| 13.85                                                                    | Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound ) content.                                                                                                                              |      |          |       |                  |
| 13.85.1                                                                  | With ready mixed gray primer on any surface having VOC content less than 50grams/ litre                                                                                                                                                                 | Sqm  | 923      | 57.05 | 52657.15         |
|                                                                          | TOTAL INCLUDING GST AS PER DSR RATES (DSR rates are inclusive of GST)                                                                                                                                                                                   |      |          |       | 169096.45        |
|                                                                          | Add escalation at 3.5% per year to bring the rates of 2018 to 20121. Total escalation – 10.5 %                                                                                                                                                          |      |          |       | 17755.13         |
|                                                                          | <b>GROSS TOTAL</b>                                                                                                                                                                                                                                      |      |          |       | <b>186851.58</b> |
|                                                                          | Contractor to quote percentage on GROSS TOTAL , Above (+)/ At Par/ Below (-)                                                                                                                                                                            |      |          |       |                  |
|                                                                          | Percentage in words                                                                                                                                                                                                                                     |      |          |       |                  |
|                                                                          | GST at 18% from above amount will be reimbursed only after submission of B2B return.                                                                                                                                                                    |      |          |       |                  |
|                                                                          |                                                                                                                                                                                                                                                         |      |          |       |                  |
|                                                                          |                                                                                                                                                                                                                                                         |      |          |       |                  |
|                                                                          |                                                                                                                                                                                                                                                         |      |          |       |                  |
|                                                                          | Signature of Contractor with cel No.                                                                                                                                                                                                                    |      | Seal     |       |                  |